

NOTICE
TOWN OFFICIALS MEETING
TOWN OF ONEIDA, OUTAGAMIE COUNTY

NOTICE, is hereby given that the Town of Oneida, Outagamie County, will hold a Town Officials Meeting on Thursday, April 6, 2023 at 10:30 A.M. The meeting will be held at, Town of Oneida, N6593 County Rd H Oneida, WI 54155

AGENDA: Accepting of bid regarding hot asphalt mix bidding for approximately 2.5 miles. Including pulverized asphalt pavement, blacktop and shouldering.

Posted on Monday, March 17, 2023

Posted at: Town of Oneida Town Hall
Town of Oneida Fire Station
Town of Oneida website: www.townofoneida.org

See Specification Below

SPECIFICATIONS:

ASPHALT PAVING PROJECT

TOWN OF ONEIDA, OUTAGAMIE COUNTY, WISCONSIN

HOT MIX BID

Scope of work

Ray Road (Curve to Bridge)

Ray Road (HWY 55 to Advent Rd)

Ranch Lane

Ranch Lane Cul-de-sac

TECHNICAL SPECIFICATIONS:

HOT MIX

Pulverize asphalt pavement and the minimum of 4 inches of base

Place a 3 1/2-inch compacted asphalt mat in two lifts with a 2" 3LT 58-28S Lower Layer and 1.5" 4LT 58-28S upper Layer.

Asphalt Concrete Pavement will meet the most Current State of Wisconsin Department of Transportation Standard Specification of Highway and Structure Construction, Section 460-E1

Projected start date for project is May 1, 2023 and deadline is September 30, 2023.

Insurance: The contractor shall furnish and deliver to the Town of Oneida a certificate of insurance for worker's compensation and an umbrella certificate of liability and property insurance in the minimum amount of \$1,000,000.00 prior to awarding bids. The Town Board of the Town of Oneida reserves the right to accept and/or reject and to accept any proposal which they deem most favorable to in the interest of the Town.

Town of Oneida 2023 Road Resurfacing

Ray Road (Curve to Bridge) 5,892' x 22' 1.12 miles

Line #	Bid Item #	Description	Quantity	UOM	Unit Price	Total
1		Pulverize Existing and reshape		SY		\$
2		2" Compacted HMA 3LT 58-28S Lower Layer		TN		\$
3		1.5" Compacted HMA 4LT 58-28S Upper Layer		TN		\$
4		Tack		GA		\$
5		2' CABG Shoulder ¾"		TN		\$
SUBTOTAL						\$

Ray Road (HWY 55 to Advent Rd) 6,487' x 22' 1.23 mile

Line #	Bid Item #	Description	Quantity	UOM	Unit Price	Total
1		Pulverize Existing and reshape		SY		\$
2		2" Compacted HMA 3LT 58-28S Lower Layer		TN		\$
3		1.5" Compacted HMA 4LT 58-28S Upper Layer		TN		\$
4		Tack		GA		\$
5		2' CABG Shoulder ¾"		TN		\$
SUBTOTAL						\$

Ranch Lane 320' x 22' .06 miles

Line #	Bid Item #	Description	Quantity	UOM	Unit Price	Total
1		Fine Grade existing gravel base		SY		\$
2		2" Compacted HMA 3LT 58-28S Lower Layer		TN		\$
3		1.5" Compacted HMA 4LT 58-28S Upper Layer		TN		\$
4		Tack		GA		\$
5		2' CABG Shoulder 3/4"		TN		\$
					SUBTOTAL	\$

Ranch Lane Cul-de-sac

Line #	Bid Item #	Description	Quantity	UOM	Unit Price	Total
1		Fine Grade existing gravel base		SY		\$
2		2" Compacted HMA 3LT 58-28S Lower Layer		TN		\$
3		1.5" Compacted HMA 4LT 58-28S Upper Layer		TN		\$
4		Tack		GA		\$
5		2' CABG Shoulder 3/4"		TN		\$
					SUBTOTAL	\$

Bid TOTAL	\$
------------------	-----------

Signature : _____

Title : _____

Date: _____